

KANSAS

Form CP-3  
Rev. 6-4-68

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

12-4-78

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -145-00793-0000 (of this well)

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Phinney Well No. 1

Location SW SW NE Sec. 34 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3854'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 3:45 P Day 1 Month XX 12 Year 1978

The above well was plugged as follows:

Total Depth 3854' 8 5/8 csg set 948' cwc 500 sk.

5 1/2 csg set 3849' cw 100 sk cem. Sand back to 3825' -dumped 4 sk cem W/dump bailer.

Cutoff & recovered A/2029' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs

hulls -released cementing plug & capped with 110 sk 50-50 poz 6% & shutin.

MPP 450 lbs. SIP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 12-6-78  
INV. NO. 8670 W