

P

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

12-4-78

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -145-00795.0000 (of this well) DEC 4 1978

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Phinney Well No. 3

Location NW SE NE Sec. 34 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3869'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67624 License No. 683

Operation Completed: Hour 11 A Day 1 Month 12 Year 1978

The above well was plugged as follows:

Total Depth 3869' 8 5/8 csg set 1023' cwc. 425 sk.

5 1/2 csg set 3866' cw 200 sk cem.

Cutoff & recovered 2527' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 50 sk 50-50 poz 6% -displaced

with 20 sk gel & water W/100 lbs hulls -released cementing plug & capped with

110 sk 50-50 poz 6% & shutin. MPP 800 lbs. SIP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Reo Massey  
Well Plugging Supervisor

DATE 12-6-78

INV. NO. 8669-W