

TO  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 Bitting Building  
Wichita, Kansas

File 31-33.

Location W. 1/4 NW 1/4

Sec. 9 Twp. 21 Rge. 6 W.

*Abandoned oil well.*

I have today completed supervision of plugging of:

Well No. 1 Lease C. Walsten  
Operator Phillips Petroleum Co. address 610 E. Ellingham Bldg  
Field Witch County Rice  
Total Depth 3497' Feet. Started plugging 1-18-39;


(Describe briefly the manner in which well was plugged)

*Cable tool hole. Couldn't clean out hole from 3140' to bottom at 3497' top of chat. Hole filled with casing & heavy mud from 3497'-3140'. Plug rock & 40' cement from 3140'-3100'. Filled with heavy mud from 3100' to top of hole.*

Expense incurred as follows: 2-3-39

Date <u>1-18-39</u> *Day <u>1/4</u>	Mileage <u>40</u>
Date <u>1-20-39</u> *Day	Mileage <u>40</u>
Date <u>1-26-39</u> *Day	Mileage <u>40</u>
Hotel, meals, etc. \$ <u>1-30-39</u>	<u>23</u>
<u>1-31-39</u>	<u>40</u>
*Show as 1/4, 2/4, 3/4, or 4/4.	<u>30</u>
	<u>112</u>

FILED  
2 21 6  
LOOK PAGE 4 LINE 18



Guy W. Hershing  
Conservation Agent

P. O. Lyons Kansas Date 2-2-39.

*Plug rock & 15' cement below fresh water @ 150'. Plug rock & 10' cement @ base of Celler.*

*Mr Earl Allen, Canton Kansas.  
In charge for operator.*

Phillips Petroleum Co  
Rice Co