

608 S. Market, Room 2070  
Wichita, KS 67202

15.185.22591.0000

LEASE NAME Snider I

RECEIVED

SEP 28 2001

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
3630 Ft. from S Section Line  
4290 Ft. from E Section Line

KCC WICHITA

EASE OPERATOR Vess Oil Corporation

SEC. 3 TWP. 21S RGE. 11W (E) or (W)

ADDRESS 8100 E. 22nd. St. N. #300 Wichita, Kansas 67226

COUNTY Stafford

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed 6/89

Character of Well Oil

Plugging Commenced 8-15-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-16-01

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3318 Bottom 3358 T.D. 3358'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Sh. Oil & SW	3318	58			
				8-5/8"	240'	None
				4-1/2"	3318'	1850'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side.  
Plugged off bottom with sand to 3220' and 4 sks. cement. Shot pipe @2000' & 1850', pulled up to 720', pumped 8 sks. gel and 50 sks. cement, pulled up to 270', pumped 50 sks. cement, pulled up to 40' and circulated 10 sks. cement. 60/40 pos, 6% gel Plugging Complete/

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]


(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of August, 2001

[Signature]  
Notary Public

My Commission Expires:

COPY



# ALLIED CEMENTING CO., INC.

7944

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

15.185.22591.0000

SERVICE POINT:

GREAT BEND

DATE <u>08-16-01</u>	SEC. <u>3</u>	TWP. <u>21s</u>	RANGE <u>11W</u>	CALLED OUT <u>11:00/AM</u>	ON LOCATION <u>12:15/PM</u>	JOB START <u>12:30/PM</u>	JOB FINISH <u>2:00/PM</u>
LEASE <u>SUNDER</u>	WELL # <u>I#1</u>	LOCATION <u>So Equipwood to STAFFORD Co.</u>			COUNTY <u>STAFFORD</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)		<u>LINE 4 1/2 E 1/2 SO</u>					

CONTRACTOR MIKES TESTING + SALVAGE OWNER LESS OIL CORP.

TYPE OF JOB TRG WHITE PULPING

HOLE SIZE 7 7/8" T.D. 3358'

CASING SIZE 4 1/2" DEPTH 3318'

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

CEMENT AMOUNT ORDERED 110 bags 60/40 Poz. 6862  
8 bags GEL  
USEN ALL MATERIAL

COMMON	<u>66</u>	@	<u>10.65</u>	<u>438.90</u>
POZMIX	<u>44</u>	@	<u>3.55</u>	<u>156.20</u>
GEL	<u>14</u>	@	<u>10.00</u>	<u>140.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
HANDLING	<u>124</u>	@	<u>1.10</u>	<u>136.40</u>
MILEAGE	<u>22</u>			<u>109.12</u>

EQUIPMENT

PUMP TRUCK CEMENTER BUD

# 120 HELPER BLAINE

BULK TRUCK

# 341 DRIVER LADAY

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

RECEIVED

TOTAL \$ 980.62

SEP 28 2001

SERVICE

KCC WICHITA

REMARKS:

1 1/2" HANGING AT 720 FT MIX SAND GEL  
(2000S SWAB TO GEL WHITE MIXED)  
SWAB 60/40 POZ 6862 GEL DISPLACE TO  
BALANCE 2ND PLUG 4 1/2" AT 270 FT  
MIX SAND 60/40 POZ 6862 GEL DISPLACE  
TO BALANCE TOP PLUG AT 40 FT.  
MIXED 100% 60/40 POZ CEMENT  
CIRCULATED

DEPTH OF JOB	<u>720'</u>			
PUMP TRUCK CHARGE				<u>475.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>22</u>	@	<u>3.00</u>	<u>66.00</u>
PLUG		@		
		@		
		@		

TOTAL \$ 541.00

CHARGE TO: LESS OIL CORP

STREET 8100 E 22ND ST No. #300

CITY WICHITA STATE KS ZIP 67226

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX	<u>\$ 27.38</u>		
TOTAL CHARGE	<u>\$ 1619.00</u>		
DISCOUNT	<u>\$ 152.16</u>		IF PAID IN 30 DAYS

SIGNATURE [Signature]

[Signature]  
PRINTED NAME

Net \$ 1166.84  
\$ 1166.84