

STATE OF KANSAS  
OIL AND GAS CORPORATION COMMISSION  
100 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

15.185.22591.0000

API NUMBER 15-185-22591-0000

LEASE NAME Snider I #

WELL NUMBER 1

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 3 TWP. 21S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-15-01

Plugging Completed 8-16-01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. N. #300 Wichita, Kansas 67226

PHONE#(316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O. 3358'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	240'	None
				4-1/2"	3318'	1850'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 3220' and 4 sks. cement. Shot pipe @2000' & 1850', pulled up to 720', pumped 8 sks. gel and 50 sks. cement, pulled up to 270', pumped 50 sks. cement, pulled up to 40' and circulated 10 sks. cement, 60/40 pos, 6% gel. Plugging Complete/

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED

SUBSCRIBED AND SWORN TO before me this 28th day of August, 2001

AUG 29 2001

[Signature]  
Notary Public

KCC Wichita Commission Expires:

NOTARY PUBLIC - State of Kansas  
IRENE HERZBERG  
My Appt. Exp. 8-24-05

Form  Revised 05-

OR