

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-185-23122-0000
LEASE NAME Snider
WELL NUMBER "C" 1-3

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

330 Ft. from North Line of Section
1650 Ft. from West Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 50' W of Nw Ne Nw of
ADDRESS P.O. Box 780167 Section 3 Township 21s Range 11w
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Stafford
PHONE # 316-684-8481 Date Well Completed March 29, 2001
Character of Well Dry and Abandoned Date Plugging Commenced March 29, 2001
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed March 29, 2001

The plugging proposal was approved on March 28, 2001 (date)
by Scott Alberg (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3560

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	185	and		
Redbeds	Shale	185	225	8-5/8"	209.14	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well using 175 sx 60/40 Poz, 6% Gel as follows: Heavy mud from 3560' to 3400', then 40sx, heavy mud from 3400' to 600', then 50sx, heavy mud from 600' to 250', then 50sx, heavy mud from 250' to 40', then 10sx cement to surface. Plug down at 10:00pm on 03/29/01 by Acid Services, ticket # 03301. Plugged rathole with 15sx, mousehole with 10sx.

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice-President of Sterling Drilling Company)


(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 30th day of March 2001

RECEIVED
STATE CORPORATION COMMISSION

APR - 2 2001

Pamela S. Fields
(Notary Public)
CONSERVATION DIVISION
Wichita, Kansas



My Commission Expires: 1-28-02

Form CP-4
Revised 12-92

OR

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG**Snider "C" 1-3**

LOCATION: 50' W of Nw Ne Nw of Section 3 T 21s R 11w
API: 15-185-23122-0000 Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 21-Mar-01
COMPLETED: 29-Mar-01

TOTAL DEPTH: **DRILLER** 3560 FEET
LOGGER 3558 FEET

Ground Elevation: 1772
KB Elevation: 1781

LOG

0 -	4 FEET	Top Soil and Sand
4 -	8 FEET	Clay
8 -	27 FEET	Sand and Gravel
27 -	32 FEET	Clay
32 -	62 FEET	Sand and Gravel
62 -	185 FEET	Sand
185 -	505 FEET	Redbeds
505 -	526 FEET	Anhydrite
526 -	1350 FEET	Redbeds, Shales and Salt
1350 -	3452 FEET	Limestone, Shale and Dolomite
3452 -	3480 FEET	Arbuckle
3480 -	3560 FEET	Chert

CASING RECORDS**Surface Casing**

Spud @ 10:45 am on 03/21/01 . Drilled 12-1/4" hole to 225'. Ran 5 joints of new 23# 8-5/8" surface casing, tallied 209.14', set at 220' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC. Plug down at 3:00 pm on 03/21/01 by Acid Services. Ticket #03297. Cement did circulate.

Plugging Information.

Plugged well using 175 sx 60/40 Poz, 6% Gel as follows: Heavy mud from 3560' to 3400', then 40sx, heavy mud from 3400' to 600', then 50sx, heavy mud from 600' to 250', then 50sx, heavy mud from 250' to 40', then 10sx cement to surface. Plug down at 10:00pm on 03/29/01 by Acid Services, ticket # 03301. Plugged rathole with 15sx, mousehole with 10sx.

DEVIATION SURVEYS

1/2 degree(s) at	225	feet
1-3/4 degree(s) at	3153	feet
7/8 degree(s) at	3250	feet
1 degree(s) at	3560	feet

RECEIVED
STATE CORPORATION COMMISSION

APR - 2 2001

CONSERVATION DIVISION
Wichita, Kansas