


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

Stafford County. Sec. 3 Twp. 21 Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner F. G. Holl
Lease Name Snider Well No. 2
Office Address 6427 E. Kellogg, Wichita, Kansas 67207
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed July 27 19 70
Application for plugging approved _____ 19____
Plugging commenced August 27 19 70
Plugging completed September 4 19 70
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3347 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	252'	8 5/8"	252'	none
		0	3344'	4 1/2"	3344'	2444.41

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3300' and dumped 4 sacks of cement.

Squeezed well with 15 sacks of mud and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 70

My commission expires Feb. 10, 1971

Serge A Meyer
Notary Public.

WELL LOG

DATE COMMENCED: June 23, 1967
 DATE COMPLETED: July 1, 1967

F. G. Holl
 SNIDER #2
 SW SW NW Sec. 3-21-11w
 Stafford County, Kansas

0 - 90' Surface Sand, Clay, Sand
 90 - 183' Shale & Sand
 183 - 496' Red Bed
 496 - 515' Anhydrite
 515 - 618' Red Bed
 618 - 1615' Shale & Shells
 1615 - 1975' Lime Shale
 1975 - 2670' Shale & Lime
 2670 - 2925' Lime
 2925 - 2929' Shale
 2929 - 2950' Lime Shale
 2950 - 3052' Shale
 3052 - 3070' Lime Shale
 3070 - 3331' Lime
 3331 - 3347' Dolomite

ELEVATION: 1765 K.B.

FORMATION DATA

Anhydrite	496
Heebner	2925
Brown Lime	3052
Lansing	3070
Arbuckle	3331
RTD	3347

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 28 1970
 CONSERVATION DIVISION
 Wichita, Kansas

SURFACE CASING: Set 8-5/8"
 at 252 with 225 sacks cement.

PRODUCTION CASING: Set 4 1/2"
 at 3344' with 125 sacks pozmix

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

L. O. Chubb of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.


 L. O. Chubb

Subscribed and sworn to before me this 7th day of July, 1967.

My Comm. Expires:

4-11-70


 Notary Public