


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 3 Twp 21 Rge. 11 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NW NW SW
Lease Owner F. G. Holl
Lease Name Fair Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 10, 1958
Application for plugging filed September 10, 1958
Application for plugging approved September 10, 1958
Plugging commenced September 10, 1958
Plugging completed September 10, 1958
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3502 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	300'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Set bridge and plug at 279'. Run 20 sacks of cement through drill pipe 279'--up. Set bridge plug at 35' ran 10 sacks of cement 35' to base of cellar. Also dumped two sacks in rat hole. Job completed 7 a.m. september 10, 1958.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Isern Drilling Company
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
I, M. M. SHROPSHIRE (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Shropshire
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 58

My commission expires February 10, 1959

George Meyer
Notary Public.

PLUGGING
FILE SEC 3 T 21 R NW
BOOK PAGE 29 LINE 25

WELL LOG

F. G. HOLL - OWNER - FAIR #1
NW NW SW Section 3, Township 21, Range 11
Stafford County, Kansas

ELEVATION: 1769 KB

PIPE RECORD:

8 5/8" set at 300'
Cemented with 250 sacks cement
and 500# of Calcium Chloride

Rotary Commenced 9-2-58
Completed 9-10-58

Figures indicate bottom of formation:

- 0 to 10 cellar
- 125 sand & clay
- 304 Red Rock
- 1015 Shale & shells
- 1200 salt
- 1350 shale & shells
- 1504 Lime & shale
- 1553 Sand Lime & Shale
- 2020 Lime & shale
- 2655 shale & shells
- 3270 lime & shale
- 3356 lime
- 3502 Conglomeration
- 3502 TD

STATE OF KANSAS)
COUNTY OF BARTON) SS

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1958

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 12th Day of September, 1958.

George A. Meyer
Notary Public

My Commission expires February 10, 1959.

PLUGGING			
FILE	SEC	3	T. 21 R. 11 W.
BOOK	PAGE	129	LINE 25