


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 3 Twp. 21 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner F. G. Holl  
Lease Name Snider B Well No. 1  
Office Address 6427 E. Kellogg, Wichita, Kansas 67207  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 19  
Application for plugging filed July 9 19 70  
Application for plugging approved 19  
Plugging commenced August 31 19 70  
Plugging completed September 4 19 70  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3371 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	250'	8 5/8"	250'	none
		0	3370'	4 1/2"	3370'	2708.57

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 3300' and dumped 4 sacks of cement.

Squeezed well with 15 sacks of mud and 100 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor PIPE PULLERS, INC.  
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September 19 70

My commission expires Feb. 10, 1971  
George A. Meyer Notary Public.

W E L L L O G

DATE COMMENCED: June 15, 1970  
 DATE COMPLETED: June 21, 1970

F. G. Holl  
 SNIDER B-1  
 SE/4 SE/4 SE/4  
 Sec. 3-T21s-R11w  
 Stafford County, Kansas

0 - 175' Sand - Shale  
 175 - 476' Red Bed  
 476 - 498' Anhydrite  
 498 - 1316' Shale - Shells  
 1316 - 1530' Lime & Shale  
 1530 - 1715' Shale & Lime Breaks  
 1715 - 2543' Lime - Shale  
 2543 - 2644' Lime  
 2644 - 2922' Lime & Shale  
 2922 - 2926' Shale  
 2926 - 2940' Lime & Shale  
 2940 - 2955' Lime  
 2955 - 3054' Shale  
 3054 - 3076' Lime & Shale  
 3076 - 3338' Lime  
 3338 - 3348' Lime & Shale  
 3348 - 3371' Dolomite  
 3371 RTD

ELEVATION: 1767 K.B.

FORMATION DATA

ANHYDRITE	476
HOWARD	2543
TOPEKA	2644
HEEBNER	2922
TORONTO	2940
DOUGLAS	2955
BROWN LIME	3054
LANSING	3076
BASE LANSING	3338
ARBUCKLE	3348
RTD	3371

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 10 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

SURFACE PIPE: Set new 20#  
 at 250' with 225 sacks pozmix,  
 2% gel.

PRODUCTION CASING: Set used  
 4 1/2" at 3370' with 60 sacks  
 common cement and 600 gals.  
 latex, 1/4# floseal per sack.

A F F I D A V I T

STATE OF KANSAS  
 COUNTY OF BARTON ) ss

Larry Curtis, of lawful age, does swear and state that the facts  
 and statements herein contained are true and correct to the best of his  
 knowledge.

Larry Curtis

Subscribed and sworn to before me this 26 day of June 1970

My Commission Expires:  
April 11, 1974

Dorothy M. Hague  
 Notary Public