

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,375-0000

LEASE NAME Snider

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 3 TWP. 21 RGE. 11 (X) or (W)

COUNTY Stafford

Date Well Completed 6-17-86

Plugging Commenced 6-17-86

Plugging Completed 6-17-86

LEASE OPERATOR Ainsworth Company

ADDRESS P.O. Box 1269 Colorado Springs, CO 80901

PHONE# (303) 576-5300 OPERATORS LICENSE NO. 6030

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Jack Luthi
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3344'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 600' w/50 sacks 60/40pozmix 6% gel 3% cc. thru drill pipe

Next Plug: @ 330' w/50 " " " " " " "

Top Plug: @ 40' w/good bride and 10 sacks cement

15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Larry Curtis (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION


(Signature) Larry Curtis

(Address) Box 823 Great Bend, KS 67530

JUN 24 1986

SUBSCRIBED AND SWORN TO before me this 23 day of June, 1986

Dorothy M. Hague
Notary Public



DRILLER'S WELL LOG

DATE COMMENCED: June 11, 1986
 DATE COMPLETED: June 17, 1986

Ainsworth Company
 SNIDER #1
 NE NE SE
 Sec. 3, T21S, R11W
 Stafford County, Ks.

ELEVATION: 1764'

0 - 473' Surface soil, Sand, Shale
 473 - 494' Anhydrite
 494 - 2920' Shale & Lime
 2920 - 2935' Shale & Lime
 2435 - 2951' Lime
 2951 - 3047' Shale
 3047 - 3063' Lime & Shale
 3063 - 3299' Lime
 3299 - 3333' Shale & Lime
 3333 - 3344' Dolomite
 3344' RTD

FORMATION DATA

Anhydrite	473'
Heebner	2920'
Toronto	2435'
Douglas	2951'
Br. Lime	3047'
Kansas City	3163'
Base K.C.	3299'
Arbuckle	3333'
RTD	3344'

Surface Pipe: Set new
 8-5/8", 20# pipe @299'
 w/200 sacks 60/40 pozmix
 2% gel 3% cc.

A F F I D A V I T


STATE OF KANSAS
 COUNTY OF BARTON) ss

Larry Curtis of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 23 day of June 1986.

Dorothy M. Hague
 Notary Public



RECEIVED
 STATE CORPORATION COMMISSION

JUN 24 1986

CONSERVATION DIVISION
 Wichita, Kansas