

WELL LOG

Date started 6-20-61
Date completed 6-28-61

Snyder #2
Section 3, Twp. 21, Range 11W
SW, SW, SE Stafford County

Well plugged at 240' with 1/2 sack
cottonseed hulls on top on 20 sacks of
cement spotted through drill pipe and at
40' with 1/2 sack of cottonseed hulls on top
of 10 sacks of cement.

| | | |
|---------------------|-------|---------|
| Elevation | 1777' | KB |
| Heebner | 2930' | (-1153) |
| Toronto | 2948' | (-1171) |
| Douglas | 2964' | (-1187) |
| Brown lime | 3065' | (-1288) |
| Lansing | 3084' | (-1307) |
| Base/ Kansas City | 3321' | (-1544) |
| Shaley Conglomerate | 3342' | (-1565) |
| Arbuckle | 3358' | (-1581) |
| Total Depth | 3380' | (-1603) |

- 0' - 250' Sand and clay
- 250' - 880' Shale and shells
- 880' - 1425' Shale
- 1425' - 1565' Lime - Shale
- 1565' - 1815' Brk. lime
- 1815' - 2485' Shale and lime
- 2485' - 2720' Shale
- 2720' - 2828' Lime and shale
- 2828' - 2915' Lime
- 2915' - 3143' Lime and shale
- 3143' - 3358' Lime
- 3358' - 3372' Arbuckle

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1961
CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

State of Kansas County of Barton

I A. M. Jones certify that the above is a true and correct long as reflected by
the daily drilling reports of the Jones Drilling Company.

By: *A. M. Jones*
A. M. Jones

Subscribed and sworn before me this 31st Day of July, 1961.

John W. Poos
Notary Public John W. Poos

My commission expires April 11, 1963.