

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,626.0000

LEASE NAME Sleeper-Fair

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3

330 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR John O. Farmer, Inc.

SEC. 3 TWP. 21S RGE. 11 (E/W) (W)

ADDRESS P. O. Box 352, Russell, Kansas 67665

COUNTY Stafford

PHONE#(913) -483-3144 OPERATORS LICENSE NO. 5135

Date Well Completed 11/26/89

Character of Well D&A

Plugging Commenced 11/26/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/26/89

The plugging proposal was approved on 11-26-89 (date)

by Mike Spain (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	322'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3400'-3340' 10 sks cement @ 40'
 50 sks cement @ 3340' 15 sks in rathole
 50 sks cement # 600' 15 sks in wtr. well
 40 sks cement @ 350'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.


STATE OF KANSAS COUNTY OF RUSSELL, ss. Wichita, Kansas

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 89



Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

Commission Expires: February 6, 1992

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: John O. Farmer, Inc.
P. O. Box 352
Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Sleeper-Fair WELL #3

LOCATION: SE SW SW
Section 3-21S-11W
Stafford County, Kansas

LOGGERS TOTAL DEPTH: 3402'

ROTARY TOTAL DEPTH: 3400'

COMMENCED: 11/20/89

CASING: 8-5/8" @ 322' w/225 sks cement

ELEVATION: 1771' K.B.

COMPLETED: 11/26/89

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand	188'	Heebner	2928'
Shales & Red Bed	275'	Toronto	2948'
Dakota Sand	301'	Lansing-Kansas City	3074'
Shales & Red Bed	493'	Arbuckle	3334'
Anhydrite	494'	R.T.D.	3400'
Topeka	2650'		


RECEIVED
STATE DEPARTMENT OF REVENUE

NOV 30 1989

COMMERCIAL TAX DIVISION
TOPEKA, KANSAS


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on November 28, 1989.

My commission expires: February 6, 1992.




Glenda R. Tiffin, Notary Public