

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-22,622-0000

LEASE NAME Sarah

WELL NUMBER 3

1650 Ft. from S Section Line

4390 Ft. from E Section Line

SEC. 3 TWP. 21S RGE. 11 (E/W)

COUNTY Stafford

Date Well Completed 11/19/89

Plugging Commenced 11/19/89

Plugging Completed 11/19/89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P. O. Box 352, Russell, Kansas 67665

PHONE# (913) -483-3144 OPERATORS LICENSE NO. 5135

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-19-89 (date)

by Case Morris (KCC District Agent's Name).

Is AC0-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3401'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	319'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3401'3390' 10 sks cement @ 40'

40 sks cement @ 3390' 15 sks rathole

50 sks cement @ 600' 15 sks water well

40 sks cement @ 350'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]


(Address) Kyle B. Branum

Box 506, Russell, KS 67665-0506

11-27-89

RECEIVED
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 89



CONSERVATION DIVISION
 Wichita, Kansas

Commission Expires: February 6, 1992

Glenda R. Tiffin
 Glenda R. Tiffin, Notary Public

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: John O. Farmer, Inc.
P. O. Box 352
Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Sarah WELL #3

LOCATION: 100' N of SE NW SW
Section 3-21S-11W
Stafford County, Kansas

ROTARY TOTAL DEPTH: 3401'

ELEVATION: 1771' K.B.

COMMENCED: 11/14/89

COMPLETED: 11/19/89

CASING: 8-5/8" @ 319' w/175 sks cement

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil, Sand & Redbed	215'	Heebner	2936'
Cedar Hills	355'	Toronto	2957'
Shale & Redbed	395'	Lansing-Kansas City	3085'
Anhydrite	493'	Conglomerate	3354'
Red Bed	521'	Arbuckle	3388'
Topeka	2655'	R.T.D.	3401'


RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1989

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.




Kyle B. Branum

Subscribed and sworn to before me on November 21, 1989.

My commission expires: February 6, 1992.





Glenda R. Tiffin, Notary Public