

API NUMBER 15-185-22637-0000

LEASE NAME Snider 'A'

WELL NUMBER #1

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

4290' Ft. from S/N Line of Section (circle one)

3021' Ft. from EW Line of Section (circle one)

SPOT LOCATION 50' W of SE, NE, NW N. 2NW. 4

LEASE OPERATOR National Petroleum Resources, Inc

ADDRESS 250 N. Rock Rd. Ste. 130

CITY, STATE, ZIP Wichita Kansas 67206

PHONE#(316) 6813515 OPERATORS LICENSE NO. 9482

SEC. 3 TWP. 21 S. RGE 11 (E) or (W)

COUNTY STAFFORD

Charater of Well OIL
 Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 1-10-90

Date Plugging Commenced April 12, 2000

Date Plugging Completed April 13, 2000

The plugging proposal was approved on April 11, 2000 (date)

by KCC #1 Kevin Stube (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation(s) Simpson SAND Depth to Top 3361.5 Bottom 3367.5 T.D. 3425

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Pipe	0	301'	8 5/8	301'	0
	Casing	0	3426.95'	5 1/2	3426.95	1282'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Sanded Back to 3180' - Set B.P. at 3160' - 1st Shot 1360' - No Good - 2nd Shot 1282'
Casing Free. pulled 2 jts., pumped 20 sx Cement at 1210', pulled 15 jts of 5 1/2, Pumped
a second cement plug, pulled 7 jts and pumped third cement plug, pulled
6 more jts of 5 1/2. Total jts pulled = 32 jts of 5 1/2

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address Box 847. Pratt KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Petroleum Reserve Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart Office Manager (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) Pratt Well Service Inc.

SUBSCRIBED AND SWORN TO before me this 24 day of April, 2000

Amy S. Robertson
 Notary Public

My Commission Expires: 3/13/04

AMY S. ROBERTSON
 Notary Public - State of Kansas
 My Appt. Expires 3/13/04

R Form CP-4
 Revised 12-5

RECEIVED
 STATE CORPORATION COMMISSION
 APR 27 2000

CONSERVATION DIVISION
 Wichita, Kansas