

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
10 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-22,574-00-00

LEASE NAME SNIDER "G"

RECEIVED  
JUN 26 2003  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

2310 Ft. from E Section Line

EASE OPERATOR VESS OIL CORPORATION

SEC. 3 TWP. 21 SRGE. 11 W (E) or (W)

ADDRESS 8100 E. 22nd. N. Bldg. 300 Wichita, Ks. 67524

COUNTY Stafford

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 6-29-03

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-30-03

When plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3356'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	240'	None
				4-1/2"	3312'	1600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each sack. Plugged off bottom with sand to 3250' and 4 sacks cement. Cut casing off @1600', pulled up to 600', pumped 10 sacks gel, 50 sacks cement, pull up to 275', pumped 50 sacks cement, pulled up to 40' and topped off with 25 sacks cement, 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts herein stated, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of June, 2003

[Signature]  
Notary Public

My Commission Expires:

