

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-22,536-0000

LEASE NAME Snider

WELL NUMBER C-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3630' Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 3 TWP. 21 RGE. 11 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. N. Bldg. 300 Wichita, Ks. 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 8-18-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-20-97

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3338'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 240'   | None       |
|           |         |      |    | 4-1/2" | 3326'  | 1600'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3100' and 4 sacks cement. Shot @2800', 2600', 2400', 2000' and 1600'. Pulled up to 600' and pumped 10 sacks gel and 50 sks cement, pulled to 270', pumped 50 sks. cement, pulled rest of pipe and circulated 15 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

8-25-97

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22 day of August, 1997

[Signature]  
Notary Public

My Commission Expires: August 24, 1997

