

API NUMBER 15-159-21, 997.0001

LEASE NAME Engelland

WELL NUMBER 1-16

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

660 Ft. from S/N Line of Section (circle one)

660 Ft. from E/W Line of Section (circle one)

SPOT LOCATION C SE SE

SEC. 16 TWP. 21 S. RGE 7 (E) or (U)

COUNTY RICE

Date Well Completed

Date Plugging Commenced March 24, '99

Date Plugging Completed March 26, '99

LEASE OPERATOR Pratt Well Service Inc.

ADDRESS P.O. Box 847

CITY, STATE, ZIP Pratt, KS 67124

PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 20, '99 (date)

by Jack Luthie Dist #2 (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation(s) Perfs 3153'-3159' Depth to Top Bottom T.D. 3470'

Show depth and thickness of all water, oil and gas formations.

Cast IRON BRIDGE Plug 3225
Elev. 1612 K.B.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Casing	0'	221'	8 5/8"	221'	0'
	Production Casing	0'	3469'	5 1/2"	3469'	2763'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

March 24, '99 Back Filled SAND to 3060', Dumped 5 sx Cement

March 25, '99 Shot 5 1/2" Casing off at 2763', Pulled 67 jts of 5 1/2" Casing

March 26, '99 Filled Hole w/ water, Ran Tubing to 1032', Acid Services Pumped 35 sx Cement
Pulled tubing back to 564', pumped 35 sx Cement, Pulled Tubing back to 280', pumped Cement
(If additional description is necessary, use BACK of this form.) to the Surface

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address Box 847, Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pratt Well Service Inc.

STATE OF Kansas COUNTY OF Pratt, KS.

Stephen E. Hart OFFICE Manager (Employee of Operator or (Operator) of above-described well, being first
sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described
well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart / Pratt Well Service

(Address) P.O. Box Pratt, Kan 67124

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1999

Kenneth W. Furgason
Notary Public

My Commission Expires: 06/19/00



RECEIVED
STATE CORPORATION COMMISSION

APR 13 1999
4-13-1999
CONSERVATION DIVISION
Wichita Kansas