

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-22,038

NE SE SE, SECTION 2 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 32081 990 FEET FROM S SECTION LINE
OPERATOR SMOKEY VALLEY RESOURCES 330 FEET FROM E SECTION LINE
NAME & RT 3, BOX 63
ADDRESS LYONS, KS 67554
LEASE NAME: RODGERS #1
COUNTY: RICE 112.65
WELL TOTAL DEPTH: 3446'
PIPE: 5 1/2" @ 3445'
SURFACE CASING: 8 5/8" @ 221'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE
ADDRESS: CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 20 MONTH: 6 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 3250' 5 SACKS
35 SACKS AT 750'
35 SACKS AT 550'
275' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: J.L.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 3:00 DAY: 20 MONTH: 6 YEAR: 1997

ACTUAL PLUGGING REPORT: SAND BOTTOM TO 3250' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2640'. PULLED TO 750', PUMPED 35 SACKS. PULLED TO 550', PUMPED 35 SACKS. PULLED TO 275', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #5614

INVOICED
DATE JUL 03 1997
INV. NO. 48493
RECEIVED
KANSAS CORPORATION COMMISSION
JUL 01 1997
CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.
Jack Luthi
JACK LUTHI

file