

6-30 15.159.21740.0000 2-070713

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-21,740

C E/2 NE SE, SECTION 2 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 32081 1650 FEET FROM S SECTION LINE
OPERATOR SMOKEY VALLEY RESOURCES 330 FEET FROM E SECTION LINE
NAME & RT 3, BOX 63
ADDRESS LYONS, KS 67554

LEASE NAME: WATSON #1 112.13
COUNTY: RICE
WELL TOTAL DEPTH: 3450' PB 3430'
PIPE: 5 1/2" @ 3445'
SURFACE CASING: 8 5/8" @ 225'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 8:30 DAY: 30 MONTH: 6 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 3368' AND 5 SACKS
35 SACKS AT 750'
35 SACKS AT 550'
275' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 1:00 DAY: 30 MONTH: 6 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3368' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2414'. PULLED TO 750', PUMPED 35 SACKS. PULLED TO 550', PUMPED 35 SACKS. PULLED TO 275', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40/POZ 4% GEL ALLIED

INVOICED
DATE JUL 03 1997
48490
6-30

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 03 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.
Jack Luthi
JACK LUTHI