

1050302

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,049- 0000

C NW NE, SEC. 24, T 28 S, R 17 W/EX
4620 feet from ~~XXX~~ SE Corner of
1980 feet from ~~XXX~~ SE Corner of
section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9668

Lease Name E.H. Ross Well # 1-24

Operator: Imperial Oil and Gas, Inc.
Name & Address 720 Fourth Financial Center
Wichita, KS 67202

County Kiowa

Well Total Depth 4870 158.28 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 471

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 3 Month: August Year: 19 84

Plugging proposal received from Randy Knott

(company name) Red Tiger (phone) 316-862-5952

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1110' with 50 sx cement

2nd plug at 540' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plug 100' water well with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:15 pm Day: 3 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1110' with 50 sx cement, 2nd plug at 540' with 50 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, plugged water well

with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

INVOICED (if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 8-14-84

INV. NO. 3080

Signed Richard W. Lacey
(TECHNICIAN)

8-7-84
RECEIVED
STATE CORPORATION COMMISSION
AUG 07 1984
CONSERVATION DIVISION
Wichita, Kansas