

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23036-00-00
Spot: SESENE Sec/Twnshp/Rge: 5-21S-11W
2400 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: MEYER Well Number: 3-5
County: STAFFORD Total Vertical Depth: 3520 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size feet: \$114.40
Surface Casing: Size 8.625 feet: 279
Production: Size 4.5 feet: 3517 WITH 160 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/05/2001 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: FG HOLL Phone: (316) 684-8481

Proposed Plugging Method: SAND TO 3209' & 4 SX CMT. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/05/2001 11:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3504'. PERFS AT 3285-88, 3295-98, 3375-78'. ANHYDRITE @ 580'. SANDED TO 3209' & 4 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED
DATE 03-12-2001
INV. NO. 2001061483

MAR 9 2001
3-9-01
CONSERVATION DIVISION
WICHITA, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2409' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

MAR 08 2001

ML

[Signature]

Form CP-213