

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23069-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 3-21S-11W  
1490 feet from N Section Line, 990 feet from E Section Line  
Lease/Unit Name: SNIDER Well Number: 2-3  
County: STAFFORD Total Vertical Depth: 3410 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 6427 EAST KELLOGG  
WICHITA, KS 67207

Conductor Pipe: Size feet: #110.83  
Surface Casing: Size 8.625 feet: 261 WITH 235 SX CMT  
Production: Size 4.5 feet: 2762 WITH 250 SX CMT  
Liner: Size feet:

Well Type: Oil Gas UIC Docket No: Date/Time to Plug: 03/06/2001 3:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: FG HOLL Phone: (316) 793-0915

Proposed Plugging Method: SAND TO 2200' & 4 SX CMT. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/06/2001 4:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 2626'. PERFS AT 2602-2652 & 2281-2398. SAND TO 2200' & 4 SX CMT. PUMP PLUGS THROUGH CASING. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED  
DATE 03-12-2001  
INV. NO. 2001061483

3-9-01  
RECEIVED  
STATE CORPORATION COMMISSION  
MAR 9 2001  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1908' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

MAR 08 2001

Form CP-073