

1 060007

11-19

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,622-0000
100' W of
SE NW SW, SEC. 3, T 21 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

1650 feet from S section line

4390 feet from E section line

Operator License # 5135

Lease Name Sarah Well # 3

Operator: John O. Farmer, Inc.

County Stafford 110.53

Name & Address P.O. Box 352

Well Total Depth 3401 feet

Russell, KS 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 819, Russell, KS 67665

Company to plug at: Hour: 12:30 p.m. Day: 19 Month: 11 Year: 19 89

Plugging proposal received from Bill Owen

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 493-520'

1st plug at top of Arbuckle with 40 sx cement, 2nd plug at 600' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 4 p.m. Day: 19 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 3390' with 40 sx cement,

2nd plug at 600' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

Water well plugged with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If necessary, do not) observe this plugging.

DATE 12-6-89

Signed Case Morris
(TECHNICIAN)

INV. NO. 26632

RECEIVED
STATE CORPORATION COMMISSION

11-22-89 NOV 22 1989

CONSERVATION DIVISION
Wichita, Kansas

15.185.22622.0000

EFFECTIVE DATE: 10-31-89

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas
NOTICE OF INTENTION TO DRILL 185-22,622

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 4 89
month day year

100' West of East
SE NW SW Sec 3 Twp 21 S, Rg 11 West

OPERATOR: License # 5135
Name: John O. Farmer, Inc.
Address: P.O. Box 352
City/State/Zip: Russell, KS 67665
Contact Person: Sam Farmer
Phone: (913) 483-3144

1650 feet from South line of Section
4390 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 8241
Name: Emphasis Oil Operations

County: Stafford
Lease Name: Sarah Well #: 3
Field Name: Snider
Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 890'
Ground Surface Elevation: 1770 (est.) feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 120'
Depth to bottom of usable water: 250'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 300'
Length of Conductor pipe required: none
Projected Total Depth: 3400'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well farm pond other

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... X Infield ... X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OMO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

If OMO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:

Exp. 4/26/90

AFFIDAVIT

250' Alt. I Req.

Ann. Trp. 3387
PUSHER Bill Owen
TD 3401 FORMATION
SURFACE PIPE 3/9 @
ANHYDRITE 493-520 ELEVATION 600
STARTING TIME & DATE 12:30 PM 11-19-89
COMPLETION TIME & DATE 4 PM 11-19-89
1st PLUG @ Top Arb 3390 FT. W/ 40 SX
2nd PLUG @ 600 FT. W/ 50 SX
3rd PLUG @ 350 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ 15 SX
CEMENT COMPANY Allied
TECHNICIAN CM
TYPE OF CEMENT 60/40 6% gal

8 5/8" - 300'
Yes WW

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1989
CONSERVATION DIVISION
Wichita, Kansas

Vertical scale from 5280 to 330 feet.

Spud date: 11-14-89 Agent: D.G.

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.