

1052383

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-22,637-0000
SE NE NW SEC. 3, T 21 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 4290 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3021 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SNIDER "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

4/13

COUNTY STAFFORD 111.31

OPERATOR LICENSE # 9482

WELL TOTAL DEPTH 3425 FEET

OPERATOR: NATIONAL PETROLEUM RESERVES PRODUCTION CSG: SIZE 5 1/2" @ 3426.92' WITH 120SX

NAME AND 250 N ROCK RD., SUITE 130 SURFACE CASING: SIZE 8 5/8" @ 280' WITH 185 SX

ADDRESS WICHITA, KS 67206

RECEIVED 4-17-00
STATE CORPORATION COMMISSION
100 17 0000

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC LICENSE NUMBER 5893
Wichita, Kansas

ADDRESS PO BOX 847, PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 13 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM _____

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531

WERE: PERFS AT 3361.5 TO 3367.5

SANDED TO 3180'. SET CIBP @ 3170'. FLOWING OIL & GAS AT 1180'. 1ST PLUG PUMPED 20 SX

CEMENT DISPLACED TO 1100'. 2ND PLUG AT 600' WITH 40 SX CEMENT. 3RD PLUG AT 310' WITH

40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 13 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SANDED TO 3180'. SET CIBP @ 3170'. FLOWING OIL AND GAS AT 1180'. 1ST PLUG PUMPED 20 SX

CEMENT DISPLACED TO 1100'. 2ND PLUG AT 600' WITH 40 SX CEMENT. 3RD PLUG AT 310' WITH

40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1282' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 4/20/00 SIGNED Richard W. Lacey
(TECHNICIAN)

INV. NO. 061619 FORM CP-2/3