

To: 1 052156 8-20
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 185-22,536.0000
NW SW NE, SEC. 3, T 21 S, R 11 WEX
3630 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5030
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

Lease Name Snider C Well / 1
County Stafford 108.49
Well Total Depth 3338 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 20 Month: 8 Year: 19 97

Plugging proposal received from Monte
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 3326' w/150 sx cement, Perfs at 3328-33, 3204-10, 3139-45, 3156-59, 3151, 3114-16'
1st plug sand back to 3100' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 600',
3rd plug pump 50 sx cement at 270',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:40 a.m. Day: 20 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3080' and dumped 4 sx cement on top of sand through bailer,

Spotted plugs through casing:
2nd plug at 600' with 10 sx gel and 50 sx cement,
3rd plug at 270' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1589' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did) ~~not~~ observe this plugging.

DATE 8-27
INV. NO. 48869

Signed Richard W. Lacy ROW J
(TECHNICIAN)

RECEIVED
KANSAS CORP COM
1997 AUG 22 4 11:11 PM