

1091013

TO: STATE CORPORATION COMMISSION

API NUMBER 15-055-21,449.0000
SW NE NE SEC. 9, T 21 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DAVIS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY FINNEY

OPERATOR LICENSE # 5506

WELL TOTAL DEPTH 2800 91.00 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 2799' WITH 550 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 223' WITH 190 SX

ADDRESS MEDICINE LODGE, KS 67104 CONDUCTOR CSG: SIZE " @ ' WITH SX

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 10:15 AM DAY: 01 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BOB MOOREHEAD

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627

WERE: BOND LOG SHOWS CEMENT 50' FROM SURFACE.

PUMP DOWN 4 1/2" CASING WITH 300 HULLS AND 150 SX CEMENT. PUMP PRESSURE AT 800#. SHUT IN WITH 600#. BACKSIDE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 01 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT

ALLIED PUMPED DOWN 4 1/2" CASING WITH 300 HULLS AND 150 SX CEMENT. PUMP PRESSURE AT 800#.

SHUT IN WITH 600#. BACKSIDE FULL OF CEMENT.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 10-26-99 60765

OCT 12 1999 10-12-99

CONSERVATION DIVISION

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3