

15.159.22116.0000

7-7

2-070714

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-159-22,116

SW SE, SECTION 2 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 32081 990 FEET FROM S SECTION LINE  
OPERATOR SMOKEY VALLEY RESOURCES 1650 FEET FROM E SECTION LINE  
NAME & 1325 HIGHWAY 56  
ADDRESS LYONS, KS 67554

LEASE NAME: ROGERS #2-2  
COUNTY: RICE  
WELL TOTAL DEPTH: 3924' 127.53  
PIPE: 5 1/2" @ 3906'  
SURFACE CASING: 8 5/8" @ 215'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 7 MONTH: 7 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 928-2943

WERE: SAND TO 3850' AND 5 SACKS  
35 SACKS AT 750'  
35 SACKS AT 550'  
275' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( X ) NONE ( )

COMPLETED: HOUR: 1:00 DAY: 7 MONTH: 7 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3850' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2400'. PULLED TO 750', PUMPED 35 SACKS. PULLED TO 550', PUMPED 35 SACKS. PULLED TO 275', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #8274

I DID OBSERVE THIS PLUGGING.

*Jack Luthi*  
JACK LUTHI  
RECEIVED  
KANSAS CORPORATION COMMISSION

FORM CP-2/3  
REV. 3/90

INVOICED

DATE JUL 22 1997

TEL. NO. 48635

SEP 22 1997

JUL 22 1997

CONSERVATION DIVISION  
WICHITA, KS