

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-22,116-0000

LEASE NAME Rice Rogers

WELL NUMBER 2-2

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 21 RGE. 6 (E) or (W)

COUNTY Rice

Date Well Completed 12-16-85

Plugging Commenced 12-16-85

Plugging Completed 12-16-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Ron Brooks Corporation

ADDRESS 6209 North k-61 Hutchinson, KS 67502

PHONE#(316) 665-0596 OPERATORS LICENSE NO. 9300

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Salina
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 500' w/35 sacks 60/40 pozmix 4% gel thru drill pipe

Next Plug: @ 265' w/50 sacks

Top Plug: @ 40' w/good bridge & 10 sacks cement

10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Larry Curtis

(Employee of Operator) or (~~XXXXXXXXXX~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry Curtis

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 23 day of December, 1985

Dorothy M. Haque
Notary Public

My Commission Expires: 4-29-86

12-26-85 DEC 26 1985

Form CP-4
Revised 08-84

DRILLER'S WELL LOG

DATE COMMENCED: December 11, 1985
 DATE COMPLETED: December 16, 1985

The Ron Brooks Corp.
 ROGER'S #2-2
 SE SE SE
 Sec. 2, T21S, R6W
 Rice County, Ks.

ELEVATION: 1548 K.B.

0 - 2573' Surface Soil, Shale, Lime
 2573 - 2577' Shale
 2577 - 2607' Lime & Shale
 2607 - 2745' Shale
 2745 - 2764' Lime & Shale
 2764 - 3175' Lime
 3175 - 3390' Shale, Lime, Chert, Sand
 3390 - 3460' Chert, Lime
 3460' RTD

FORMATION DATA

| | |
|--------------|-------|
| Heebner | 2573' |
| Douglas | 2607' |
| Br. Lime | 2745' |
| Kansas City | 2764' |
| Base K.C. | 3175' |
| Conglomerate | 3282' |
| Cong. Chert | 3379' |
| Miss. Chert | 3390' |
| Miss. Lime | 3453' |
| RTD | 3460' |

Surface Pipe: Set new 8-5/8",
 23# pipe @ 215' w/190 sacks
 60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Larry Curtis of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 23 day of December 1985.

My Comm. Expires:

4-29-86

Dorothy M. Hague
 Notary Public

DEC 23 1985