

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Rice County. Sec. 2 Twp. 21 Rge. 6 W (E) (W)  
Location as "NE/CNW/SW" or footage from lines. SW NE SW  
Lease Owner. Pat Simmons  
Lease Name. Duvall Well No. 3  
Office Address. 5252 North Broadway Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 12-22 1969  
Application for plugging filed 7-23 1969  
Application for plugging approved 7-24 1969  
Plugging commenced 8-II 1969  
Plugging completed 8-14 1969  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 3404' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						2,629'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3404' to 3360'. Dumped 6 sx of cement. Mudded hole to 150'. Made 10' of rock bridge. Dumped 30 sx of Ready-Mix cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 15 sx of Ready-Mix cement, filling to the bottom of the cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1969

My commission expires January 5, 1970

Notary Public.

15.159.19391.0000

COPY


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union Nat'l Bk Bldg., Wichita, Kansas

Company H. C. BENNETT  
Farm, Duvall No. 3

Sec. 2 T. 21 R. 6 W  
8T NE SW

Total Depth. 3404'  
Comm. 12-7-45 Comp. 12-22-46  
Shot or Treated  
Contractor.  
Issued. 2-2-46

County Rice  
KANSAS



CASING  
10 3/4" 140' Cem.  
7" 3374' Cem.

Elevation

Production Est. 15 B.

Figures Indicate Bottom of Formations.

shale & sand	60
shale & shells	145
red rock, shale & shells	300
shale, salt & shells	580
shale & shells	820
lime, shells & shale	900
shale & shells	1050
lime & shale	1240
sand, shale & shells	1290
shale & shells	1500
lime brkn	1555
shale & shells	2265
shale & lime	2435
lime	2480
lime & shale	2570
lime	2670
lime sdy & shale	2700
lime	2730
lime brkn	2790
lime	2995
lime & shale	3055
shale & shells	3080
lime	3130
shale & shells	3160
shale	3255
shale & shells	3295
shale	3325
conglomerate	3378
lime	3404
Total Depth.	

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas