


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

## WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rice County. Sec. 2 Twp. 21 Rge. 6W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW SW SW  
Lease Owner Northridge Oil Co.  
Lease Name Duvall Well No. 5  
Office Address Rx 18271 Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed 3-5 1948  
Application for plugging filed 12-17 1971  
Application for plugging approved 12-18 1971  
Plugging commenced 12-6 1971  
Plugging completed 12-8 1971  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3383' Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	SIZE	PUT IN	PULLED OUT
			5 1/2"		2,617' (2617)
			DEC 14 1971		
			CONSERVATION DIVISION		
			Wichita, Kansas		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3383' to 3360'. Dumped 5 sx of cement. Mudded hole to 210'. Made 10' of rock bridge. Dumped 35 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1971

My commission expires January 5, 1974

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg. Wichita, Kansas

COPY  
15.159.05211.0000

Company - H. O. BENNETT  
Farm - Duvall


No. 5

SEC. 2 T. 21S R. 6W  
NW SW SW

Total Depth. 3383'  
Comm. 2/21/48 Comp. 3/5/48  
Shot or Treated.  
Contractor.  
Issued. 9/4/48

County. Rice

KANSAS



CASING: 4 Jts. 8 5/8" @ 134' cem. w/160 sax - Circulated  
150 Jts. 5 1/2" @ 3375' cem. w/40 sax

Elevation. \_\_\_\_\_

Production. Est. 35 Bbls.

Figures Indicate Bottom of Formations.

sand	50
shale	75
lime, shells & shale	135
red bed & shale	165
red bed	180
shale, red bed & shells	255
sand, shale & shells	415
salt, shale & broken lime	755
shale & lime shells	815
anhydrite & shale	935
anhydrite	945
lime & shale	1175
shale & shells	1215
sandy lime	1338
lime & shale	2250
lime	2280
lime & shale	2335
lime	2608
lime & shale	2730
lime	2780
shale	2800
lime	2860
lime & shale	2880
lime	2916
broken lime	2950
lime	2990
lime & shale	3040
lime	3085
lime & shale	3106
lime	3195
broken lime & shale	3225
lime & shale	3376
lime	3383
total depth	

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1971  
CONSERVATION DIVISION  
Wichita, Kansas