


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Rice County, Sec. 2 Twp. 21 S Rge. 6 W (E) (W)
Location as "NE/CNWSW" or footage from lines C SE NW
Lease Owner DUNBAR DRILLING INC
Lease Name DUNVALL Well No. 1
Office Address 5252 N. Broadway
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed _____ 19____
Application for plugging filed Dec 13 1974 19____
Application for plugging approved Dec 13 1974 19____
Plugging commenced Dec 15 1974 19____
Plugging completed Dec 24 1974 19____
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3394 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

plug well sand back to 3300' 6 sacks
Cement Plug with rock bridge 200-215 feet
40 Sack Cement mud to top & 20 Sack Cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor DUNBAR DRILLING INC
Address 5252 N. Broadway Wichita Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
W. P. SIMMONS (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. P. Simmons
5252 North Broadway Wichita, Kansas 67219

Subscribed and Sworn to before me this 8th day of July, 1975

My commission expires Nov. 19, 1977 Frances J. Simmons Notary Public.



RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1975

CONSERVATION DIVISION
Wichita, Kansas

15.159.19389.0000

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company: HENRY BENNETT
Farm: Duvall No. 1

SEC. 2 T. 21 R. 6W
C SE NW

Total Depth. 3394'
Comr. 10-7-54 Comp. 10-21-54
Shot or Treated.
Contractor. Salina Drlg. Corp., Inc.
Issued. 1-22-55

County Rice KANSAS



CASING:
10" 149' cem w/155 sx
7" 3384' cem w/75 sx

Elevation. 1552' D.E.

Production. 28 BO & 20 BW in 24 hrs.

Figures Indicate Bottom of Formations.

collar	8
silt	20
sand	75
shale and shells	90
red bed	375
shale and shells	1110
lime and shale	1255
lime	1470
lime and shale	2440
lime	2580
broken lime	2690
lime	2780
lime and shale	2850
lime	3055
lime and shale	3080
lime	3190
lime and shale	3370
Conglomerate	3382
Mississippi	3388
Mississippi	3394
Total Depth	

Tops:	
Conglomerate	3370
Mississippi	3382

Drilled with Cable Tools to a total depth of 3394', Fracked same, made 28 bbls. oil and 20 bbls water in 24 hrs.

RECEIVED
STATE CORPORATION COMMISSION

DFC 10-19/4

CONSERVATION DIVISION
Wichita, Kansas