

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 2 Twp. 21 Rge. 6W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NW SW  
Lease Owner Northridge Oil Co.  
Lease Name Devall Well No. 2  
Office Address Bx 18271 Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 12-2 19 71  
Application for plugging filed 11-19 19 71  
Application for plugging approved 11-21 19 71  
Plugging commenced 11-24 19 71  
Plugging completed 11-29 19 71  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3404' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		2,022'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3404' to 3350'. Dumped 6 sx of cement. Mudded hole to 210'. Made 10' of rock bridge. Dumped 50 sx of cement. Mudded hole to 30'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 1971

My commission expires January 5, 1974

[Signature]  
Notary Public.

15.159.05209.0000

COPY

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company H. C. BENNETT  
Farm Duvall

No. 2

SEC. 2 T. 21 R. 6 W  
NE NW SW

Total Depth. 3404  
Comm 11-10-45 Comp. 12-2-45  
Shot or Treated.  
Contractor.  
issued. 1-19-46

County. Rice  
KANSAS



Elevation. \_\_\_\_\_

Production. Pot. 27 B.

CASING:

10 3/4" 140' Cem.  
7" 3372' Cem.

Figures Indicate Bottom of Formations.

sand, shale, shells	70
shale & shells	150
red rock, shale, shells	350
shale, shells, salt	644
shale & shells	1035
shale, lime & shells	1115
shale, shells	1210
lime sdy, shale	1235
lime brkn & shale	1325
shale & lime	1500
lime brkn & shale	1605
lime & shale	1690
lime, shells, shale	1785
shale & shells	1880
shale	1970
shale, shells	2035
shale & lime	2125
shale	2205
lime & shale	2415
lime	2440
shale & lime	2495
lime	2610
lime brkn, shale	2620
shale sdy	2695
lime brkn	2725
lime	2815
lime brkn	2855
lime	3140
lime, shale	3200
shale, lime brkn	3240
lime & shale	3280
shale & shells	3320
shale & lime	3368
chat	3404
Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1971  
CONSERVATION DIVISION  
Wichita, Kansas