

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 2 Twp. 21 Rge. 6W (E) (W)

Location as "NE/CNW/SW" or footage from lines C EL SW SW

Lease Owner H. C. Bennett

Lease Name Chilvers Well No. 1

Office Address 1212 Union National Bldg., Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced October 3 19 66

Plugging completed October 10 19 66

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back to 3370' with gravel. Dumped 7 sacks of cement. Shot pipe off at 2824'. Pulled pipe and mudded hole to 175'. Set rock bridge from 175' to 160'. Finished filling hole with 4 yards of Ready-mix-cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1966
11-9-66
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kansas, COUNTY OF Reno, ss.
Empl oyee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #1, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of October, 19 66

Notary Public: Dorothy Self

My commission expires October 18, 1969

Henry Bennett
 Ramsey #1 (Chilvers)

Sec. 2 Twp. 21, Rge. 6
 County: Rice, Kansas

Total Depth: 3380'
 Comm: 7/9/45 Comp: 7/26/45

Casing
 8 jts. 10 3/4" Set at 160'

Cement
 100 sacks

Formation:	Depth:
Clay shale	40'
Shale, shells, sand	60
Shells, shale	150
Red Bed	161
Red Bed, shale, shells	260
Shale, shells	265
Shale, shells	270
Shale, shells, lime	375
Shale, shells	550
Salt, shale, shells	815
Shale, shells	965
Lime & shale	1050
Lime, shale, sand	1145
Lime, shale	1245
Sandy lime, shale	1408
Shale, lime	1570
Shale	1635
Shale, lime	2377
Lime	2605
Lime, Shale	2808
Lime	2952
Shale, Lime	3308
Shale	3380

RECEIVED
 SEP 15 1945
 CONSERVATION DIVISION
 Topeka, Kansas

State of Kansas)
) SS
 Russell County)

I hereby certify that the above information is true and correct to the best of my knowledge.

Clara Hummel

Subscribed and sworn to before me this 30th day of July, 1945.

Genevieve Poole
 Notary Public

My Commission Expires 7/2/49.

Drilled down with cable tools to 3397