

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 2 Twp. 21 Rge. 6W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW

Lease Owner H. C. Bennett

Lease Name *Chilvers* Well No. 2

Office Address 12 12 Union Nat'l Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced *July 3* 19 *64*

Plugging completed *July 7* 19 *64*

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? *Yes*



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well *Gilbert Tomar*

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back in the 5" with gravel. Dumped 5 sacks of cement. Shot pipe off at 560'. Pulled pipe and mudded hole to 150'. Set rock bridge and finished filling with ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1964

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor: *Bert Self* (If additional description is necessary, use BACK of this sheet)
Address *Hutchinson, Kans.*

STATE OF *Kans.* COUNTY OF *Reno*, ss. *Employee* (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Bert Self*
R. R. #4, Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this *16th* day of *July*, 19 *64*

My commission expires *Oct. 18, 1965* *Alvinity Self* Notary Public.



COMPANY:

H. C. Bennett

CONTRACTOR:

Salina Drilling Company

FARM:

Chilvers, Wall #2

LOCATION:

SW SW SW, Sec. 2-21-6
Rice County, Kansas

COMMENCED:

July 15, 1953

Completed:

August 7, 1953

Elevation 1562 Ground

Ø	to	Ø	
Ø		Ø	cellar- base - R. T.
Ø		60	sand
60		139	shale & shells
139		450	shale & shells
450		610	shale & shells
610		750	soft shale
750		885	shale - lime
885		965	sand - shale
965		1215	sand - shale
1215		1400	shale - lime
1400		1540	lime - shale
1540		1680	shale - lime
1680		1980	shale - lime
1980		2165	shale - lime
2165		2320	lime - shale
2320		2430	lime
2430		2530	lime
2530		2610	lime & shale
2610		2760	shale & lime
2760		2790	shale & lime
2790		2880	lime & shale
2880		2970	lime & shale
2970		3020	lime
3020		3105	lime & shale
3105		3205	lime & shale
3205		3280	shale & lime
3280		3303	shale & lime
3303		3340	sand & shale
3340		3376	shale
3376		3401	conglomerate
3401		3403	Miss. Lime
		3403	T. D.

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1954

CONSERVATION DIVISION
Wichita, Kansas

Ø 5/8" set @

139'

Cemented with 125 sacks.

3402'

Ø 1/2" set @

Cemented with 100 sacks of Cement

SS of oil at 3403, water and oil at 3405, more water at 3408,

Total Depth 3410' D & A