

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 2 Twp. 21 Rge. 6W (E) (W)

Location as "NE/CNW/SE" or footage from lines C E/2 SE NE

Lease Owner Sterling Drilling Company

Lease Name White "C" Well No. 3

Office Address Box 127, Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 26 19 63

Application for plugging filed March 26 19 63

Application for plugging approved March 26 19 63


Plugging commenced March 26, 12:30 p. m. 19 63

Plugging completed March 26, 3:30 p. m. 19 63

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3399' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	161' set at 169' K. B.	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging orders by Gilbert Toman, Holyrood, Kansas  
Heavy mud to 155', Halliburton plug; 1/4 sack of hulls, 20 sacks regular cement through drill pipe. Heavy mud to 35', Halliburton plug, 1/4 sack of hulls, 10 sacks regular cement up to base of cellar. 2 sacks regular cement in the rathole. Plugging completed at 3:30 p. m. 3-26-63

RECEIVED  
STATE CORPORATION COMMISSION

APR 5 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company  
Address Box 127, Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner, Secretary, Sterling Drilling Co.  
Box 127, Sterling, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 19 63

My Commission Expires Jan. 22, 1966  
BERNARD LAUDERMILK

Bernard Laudermilk  
Bernard Laudermilk Notary Public.

My commission expires



GROUP EXPLORATION COMPANY  
Sterling, Kansas

WELL LOG ----- White C #3

Located: E/2 SE/4 NE/4 Section 2-21-6, Rice County, Kansas.

OWNER: Sterling Drilling Company, etal  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 3-19-63  
COMPLETED: 3-26-63

ROTARY TOTAL DEPTH: 3399'

LOG

CASING RECORD

0 - 850 Shale & Shells  
850 - 1165 Shale & Lime  
1165 - 1370 Lime  
1370 - 2230 Lime & Shale  
2230 - 3190 Lime  
3190 - 3399 Lime & Shale T.D.

Set 8 5/8" Surface Casing @ 169' with  
110 sacks HA-5.  
  
Plugged and Abandoned.

RECEIVED  
STATE CORPORATION COMMISSION

APR 5 1963

CONSERVATION DIVISION  
Wichita, Kansas