

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford

County. Sec. 5 Twp. 21 Rge. 11 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines N. W. N. W. S. W.

Lease Owner M. & L. Oil Co.

Lease Name Kasselmann Well No. 1

Office Address Brown Bldg. - Wichita- Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 11-17 19 52

Application for plugging filed 11-17 19 52

Application for plugging approved 11-17 19 52


Plugging commenced 11-17 19 52

Plugging completed 11-17 19 52

Reason for abandonment of well or producing formation Dry hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Charles Stough

Producing formation Arbuckle Depth to top 3454 Bottom 3472 Total Depth of Well 3472 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	252	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/ Mud 3472' to 250'

Howco Plug on Top of Mud @ 250'

20 Sacks Cement on Top of Plug @ 250'

Filled 3/ Mud From Top of Cement @ 250' to 15'

Howco Plug on Top of Mud @ 15'

Filled w/ 15 Sacks Cement to Surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bud Edwards Drilling Co.

Address 510 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of November 19 55

[Signature] Notary Public.

My commission expires Dec 15 1955

23-8890-s 6-51-20M

PLUGGING
FILE SEC 5 T 21 R 1134
BOOK PAGE 60 LINE 10

NOV 29 1952 11-29-52
CONSERVATION DIVISION
Wichita, Kansas

Bud Edwards  *Drilling Co.*

DRILLING CO.

DRILLERS LOG - KASSELMAN #1
LOCATED NW-NW-SW- S-21-11
STAFFORD COUNTY - KANSAS
COMMENCED RIGGING UP 11-7-52

0	30'	Surface Clay
30	50	Sand
50	220	Shale
220	235	Lime
235	252	Red Rock (Set & Cemented Surface @ 252')
252	275	Shale
275	400	Red Bed
400	1270	Shale
1270	1450	Shale w/ Lime Strks
1450	1665	Lime w/ Shale Streaks
1665	1770	Lime
1770	1805	Sand
1805	1980	Lime
1980	2320	Shale w/ Lime Streaks
2320	2520	Lime Streaked w/ Sandy Shale
2520	2820	Shale w/ Lime Streaks
2820	3012	Lime
3012	3137	Shale
3137	3372	Lime
3372	3403	Shale
3403	3438	Conglomerate
3438	3454	Simpson Shale
3454	3472	Arbuckle Lime. T.D.

Drillers Log Tops.

Top Lahsing Lime	3154
" Hebener Shale	3012
" Congolomerate	3403
" Arbuckle	3454

Well completed as Dry Hole.
Plugged Well on 11-17-52

RECEIVED
CONSERVATION COMMISSION
NOV 26 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
PAGE 69 LINE 10