


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 20 Twp. 21S Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines SW NE SE  
Circle Oil Company  
Lease Owner  
Lease Name TIEPERMAN Well No. 3  
Office Address 500 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced September 22, 1965 19  
Plugging completed September 22, 1965 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (A. Elving)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3640 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	273	8-5/8"	9/17/65	
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 250 Feet;  
Hull and HOWCO Plug and 25 sacks cement  
through drill pipe; Heavy Mud to 40 feet;  
Solid Bridge Plug and 10 sacks cement to  
bottom of cellar; 2 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 29 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray  
500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 1965

My commission expires November 26, 1966.

Louise K. Whitted  
Notary Public

DRILLERS LOGTIEPERMAN NO. 3

CASING RECORD:           COMPANY:       Circle Oil Co., Inc.       DESCRIPTION:  
8-5/8" Surface           CONTRACTOR:   Sage Drilling Co.       SW NE SE  
set @ 273' w/250       COMMENCED:   September 17, 1965     Sec. 20-21S-12W  
sax cement               COMPLETED:   September 22, 1965     Stafford Co., Kansas  
TOTAL DEPTH:            COMPLETED:   September 22, 1965  
3640'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	40	
Sand	40	220	
Shale	220	275	
Red Bed	275	659	
Anhydrite	659	688	
Shale & Shells	688	1467	
Sandy Lime & Shale	1467	2185	
Shale and Lime	2185	2939	
Lime w/Shale	2939	3370	
Lime	3370	3435	
Lime & Shale	3435	3545	
Shale, Chert & Lime	3545	3630	
Lime	3630	3640	

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 29 1965

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

*Thomas M. McCaul, Jr.*

Thomas M. McCaul, Jr.

Subscribed and sworn to before me this 27th day of September, 1965.

*Louise K. Whitted*

Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1966.