

AMENDED

TYPE OR PRINT

NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

330 Ft. from ~~S~~/N Line of Section (circle one)

1320 Ft. from ~~S~~/W Line of Section (circle one)

LEASE OPERATOR Kaiser-Francis Oil Company

SPOT LOCATION C - N/2 - N/2 - NW

ADDRESS P. O. Box 21468

SEC. 20 TWP. 21 S. RGE 12 (E) or (W)

CITY, STATE, ZIP Tulsa, OK 74121-1468

COUNTY Stafford

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Date Well Completed 1/50

Character of Well Oil

Date Plugging Commenced 12/3/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Completed 12/9/96

The plugging proposal was approved on n/a (date)

by Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? On old form if not, is well log attached? -

Producing Formation(s) Arbuckle Depth to Top 3524 Bottom 3541 T.D. 3550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Arbuckle	Oil	3524	3541	8 5/8	318	-0-
				5 1/2	3524	1821

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom w/sand to 3463' & dumped 5 sxs cmt on top. Shot 5 1/2" csg @ 2415' & worked free.

Next pipe was stuck. Shot @ 2214', 2017' & 1821'. Pipe came free @ 1821'. Pulled all pipe.

Plugged well w/400# hulls, 20 sxs gel & 50 sxs 60/40 poz cmt. Pumped add'l 125 sxs cmt down the surface pipe. Max. pressure 500#. Shut in 100#. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike's Testing & Salvage, Inc.

License No. 31529

Address P. O. Box 467, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 97

My Commission Expires DEC 28, 1997

My Commission Expires:

RECEIVED
 KANSAS CORP COM
 MAR 13 12:30