

Sinclair Prairie Oil Co
Well Log

15.185.11783.0000

Anna Moeder #1
NE/4 of NW/4, 20-21-12W, Stafford Co., Kas.
510 ft fm East 330 ft fm South lines
Elev. 1862'

Harbar Drilling Co-rotary tools
Began drlg Apr. 6, 1944
Comp. drlg Apr. 23, 1944
T.D. 3750' dry hole in Arbuckle.

Drillers Log

Surface Clay	40'
Sand	100
Sandy Shale	150
Shale & Red Bed	295
Set 10-3/4" 32# SS 8thd. csg at 293' w/175 sx cmt.	
Red Bed & Shells	660
Anhydrite	700
Red Bed & Shells	970
Sand & Shells	1155
Shale & Shells	1170
Salt & Shale	1325
Shale & Shells	1500
Lime	1585
Lime & Shale	1685
Lime	1730
Lime Shells & Shale	1795
Lime	1900
Lime & Shale	2010
Lime	2155
Shale & Shells	2190
Lime	2335
Shale & Shells	2630
Lime	2635
Broken lime	2710
Shale	2745
Lime-broken	2790
Lime & Shale	2865
Lime	2950
Lime-hard brown	2963
Lime-soft grey	2995
Lime-hard brown	3015
Lime	3130
Lime & Shale	3305
Lime	3435
Lime-broken	3460
Lime	3493
Lime-broken	3532
Conglomerate	3552
Shale-green	3566
Chert	3593
Conglomerate	3618
Shale	3648
Lime-hard	3660
Conglomerate	3683
Shale & Lime breaks	3714
Lime	3750

Top Lan-Kc 3253' faint show oil 3450-55 & 3475-80

Top Cherty Conglomerate 3486 faint stain & odor in white chert 3550-55 and 3590-3600

Top Viola 3605 slight odor oil 3635-3640

Top Simpson 3650

Top Arbuckle 3695, 118' lower than east offset

Porosity 3731-3739 and 3747-3749 no show oil.

TD 3750' no shows worth testing.

All meas. derrick floor. Surface level to derrick floor was 3'6"

Hole plugged & abandoned Apr. 25, 1944

20 21-12W
115 2