


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 20 Twp. 21 Rge. 12 (E)/ (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW NW  
Lease Owner Musgrove Petroleum Corporation, Inc.  
Lease Name Carroll Well No. 3  
Office Address 407 KFH Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 29 19 52  
Application for plugging filed January 29 19 52  
Application for plugging approved January 29 19 52  
Plugging commenced January 29 19 52  
Plugging completed January 29 19 52  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3617 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface				8-5/8"	288'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled w/heavy rotary mud at 270'.  
Set first plug at 270', cemented w/15 sacks.  
Set second plug at 35', cemented cap w/10 sacks.

2-6-52

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation, Inc. FEB 27 1952  
Address 407 KFH Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, SS.  
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
407 KFH Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of February, 1952.

Notary Public.

My commission expires July 9, 1952.



CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: Carroll #3  
 LOCATION: NW SW NW Section 20-21-12W  
 Stafford County, Kansas  
 COMMENCED: January 14, 1952  
 COMPLETED: January 29, 1952

0	240	Sand
240	685	Red bed and shells
685	755	Anhydrite, shells, shale
755	1120	Shale, red bed and shells
1120	1415	Shale and shells
1415	1520	Shale and lime
1520	1600	Lime
1600	1715	Shale and shells
1715	1815	Lime and shale
1815	2153	Lime
2153	2605	Shale and shells
2605	2640	Lime and shale
2640	2710	Shale and shells
2710	2880	Shale and lime shells
2880	3205	Shale and lime
3205	3280	Shale and shells
3280	3520	Lime
3520	3617	Conglomerate - lime and shale, chert
	3617	Rotary Total Depth

Set 288' of 8-5/8" surface casing, cemented with 225 sacks.  
 Dry and Abandoned.

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Carroll #3, Section 20-21S-12W, Stafford County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this fourth day of February, 1952.

My Commission expires July 9, 1952.

Mary Len Rogers  
 Notary Public

RECEIVED  
 FEB 6 X 1952

PLUGGING  
 FILE SEC 20-21-12W  
 BOOK PAGE 14 LINE 6