

15-185-13089-00-00

16


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County. Sec. 20 Twp. 21 Rge. 12 (E) W

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Musgrove Drilling Co.  
Lease Name Carroll Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed July 29 1949  
Application for plugging filed July 13, 1960  
Application for plugging approved July 15, 1960  
Plugging commenced 8-15-60 1960  
Plugging completed 8-19-60 1960  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3567 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261'	None
				5-1/2"	3563'	2827'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3450' and found it clear.  
Ran 180 gal. of sand to 3275' and dumped  
5 sacks of cement with dump bailer.  
Pulled 5 1/2" casing, checked fluid to 30',  
bailed hole to 240', set 10' rock bridge  
to 230' and ran 20 sacks of cement. Mudded  
hole to 40', set 10' rock bridge to 30' and  
ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO.  
Address CHASE, MK KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas

SUBSCRIBED AND SWORN to before me this 24th day of August, 1960

My commission expires May 20, 1964  
Milton J. Volin Notary Public.



INVOICE  
 NOW ANSCHUTZ DRILLING CO., INC.  
**A-B-W DRILLING COMPANY, INC.**  
 Box 615 — Eddy Building  
 HAYS, KANSAS

15.185.13089.0000

Invoice No. \_\_\_\_\_

TO: \_\_\_\_\_ Date \_\_\_\_\_

WELL LOG  
 Carroll #1 - Stafford County, Kansas  
 S<sup>1</sup>/<sub>4</sub> NW<sup>1</sup>/<sub>4</sub> 20-21-12

LEASE \_\_\_\_\_

<u>FORMATION</u>		
Sand	0	275
Red bed, shells	225	260
Shale, shells	260	290
Red bed	290	600
Shale, shells	600	670
Anhydrite	670	695
Shale, shells	695	1,010
Shale, shells	1,010	1,305
Salt	1,305	1,375
Shale, shells	1,375	1,585
Lime	1,585	1,700
Lime	1,700	1,820
Lime	1,820	1,935
Lime	1,935	2,065
Lime	2,065	2,170
Lime, shale	2,170	2,330
S and L (broken)	2,330	2,545
Shale and Lime	2,545	2,650
Shale and Lime	2,650	2,785
Shale and Lime	2,785	2,840
Lime	2,840	2,915
Lime	2,915	3,000
Lime	3,000	3,075
Lime	3,075	3,108
Lime	3,108	3,215
L and S (Broken)	3,215	3,241
Lime	3,241	3,303
Lime	3,303	3,355
Lime	3,355	3,409
Lime	3,409	3,490
Lime	3,490	3,530
T. D.	3,530	3,565

Commenced: July 16, 1949  
 Completed: July 29, 1949

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUL 14 1960  
 CONSERVATION DIVISION  
 Wichita, Kansas

Casing Record:

8 5/8 OD casing set at 261 ft.  
 Cemented with 175 sax  
 5 1/2 oil string set at 3565 ft.  
 Cemented with 125 sax

STATE OF KANSAS  
 SS  
 COUNTY OF ELLIS

I hereby affirm that the above and foregoing is a true and correct copy of the log on your Carroll #1 Well located in the S<sup>1</sup>/<sub>4</sub> NW<sup>1</sup>/<sub>4</sub> of Section 20-21-12, Stafford County, Kansas.

ANSCHUTZ DRILLING CO., INC.

*[Signature]*

Subscribed and sworn to before me this

1st day of August, 1949.

My commission expires April 1950

[Signature]  
 Notary Public