

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Section Plat grid with a small 'x' in the top right cell.

Locate well correctly on above  
Section Plat

Stafford County, Sec. 20 Twp. 21 Rge. 12 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE/4 NW4 NE/4  
Lease Owner Clinton Oil Company  
Lease Name Syms #2 Well No.  
Office Address Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 9-14-64 19  
Application for plugging filed 8-9-72 19  
Application for plugging approved 8-10-72 19  
Plugging commenced 8/10/72 19  
Plugging completed 8/14/72 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 4/72 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ~~Syms #2~~ Biberstein  
Producing formation Arbuckle Depth to top 3546 Bottom 3553 Total Depth of Well 3686 Feet  
Show depth and thickness of all water, oil and gas formations. Perfs)

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: Arbuckle, oil, 3540', TD, 8-5/8, 662, none. Row 2: 5 1/2", 3655, 2521'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran sand to 3525' and ran 5 sacks of cement. Shot pipe at 2718', 2506', pulled 79 joints. Set 10' rock bridge at 300' and ran 5 yards concrete.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1972

My commission expires

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

[Signature]  
Notary Public.

## FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Sand, Clay	0	100			
Sand	100	240			
Red Bed	240	660			
Anhydrite	660	688			
Red Bed, Shale	688	935			
Shale, Lime	935	2240			
Shale	2240	2585			
Shale, Lime	2585	2934			
Lime	2934	3095			
Shale, Lime	3095	3323			
Lime	3323	3493			
Lime, Shale	3493	3570			
Lime	3570	3686			
Total Depth		3586			
Plug Back Depth		3555			

PAN AMERICAN RECORD

Cored #1, 3570-91, Lime w/spotted bleeding throughout.

Cored #2, 3591-3603, Lime w/spotted bleeding.

Cored #3, 3603-20, Lime, shale intermittent staining.

Ran logs and perf. Arbuckle formation 3551-53, 3546-48 w/4 SPT. Swb tstg 42 BO x 39 BW in 8 hours, corrected gravity 40. Ran tubing and rods pump tstg 32 BO x 126 BW, 24 hours.

Well completed 9-22-64.

Arbuckle Formation.

Perforations

3551

3553

3546

3548

Bench Mark

Zero point is 6'2" above center of side outlets in Braden Head.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas