

1 090288

*R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,098A  
C NE NW, SEC. 26, T 21 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

4620 feet from N/S section line  
3300 feet from W/E section line

Operator License # 6039

Lease Name Hall Well # 1

Operator: L. D. Davis

County Stafford 121.10

Name & Address R. R. 1, Box 183 B

Well Total Depth 3726 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D. S. & W. Well Servicing, Inc. License Number 6901

Address Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:40 am Day: 13 Month: February Year: 19 85

Plugging proposal received from Bob Strube

(company name) D. S. & W. (phone) 316-587-3361

were: 4 1/2" set at 3725' PBSD 3725' Perfs at 3347, Cement on back side at 3100

1st plug CIBP at 3295 with 40 sx cement

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 120 sx cement

STATE CORPORATION COMMISSION

FEB 15 1985

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN) CONSERVATION DIVISION, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:05 am Day: 13 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3295' with 40 sx cement, 2nd plug squeezed

well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"

rubber plug and pumped 120 sx cement

Maximum pressure 1000 psi and shut in 300

Remarks: Recovered 1498' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

**INVOICED**  
DATE 2-19-85  
7026

Signed Robert B. Barlett  
(TECHNICIAN) *She*