

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21760-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 26-21S-34W
1000 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: HIPP HEIRS Well Number: 2-26
County: FINNEY Total Vertical Depth: 3000 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY
Address: 12222 MERIT DRIVE STE 1500
DALLAS, TX 75251

Conductor Pipe: Size feet: \$ 97.50
Surface Casing: Size 8.625 feet: 271 WITH 150 SX CMT
Production: Size 5.5 feet: 3000 WITH 575 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/18/2002 1:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEROY JONES Company: MERIT ENERGY Phone: (972) 701-8377

Proposed Plugging Method: PUMP HULLS AND FILL CASING WITH CMT TO SURFACE. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/18/2002 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3000'. PERFS AT 2551-77, 2603-2756'. PUMP 500# HULLS AHEAD OF CMT. FOLLOW HULLS WITH 245 SX CMT. FILL 5 1/2" FROM 2300' TO SURFACE. PRESSURE TO 500 PSIG & SHUT IN. HOOK ONTO BACKSIDE & PUMP 5 SX CMT. PRESSURE TO 550 PSIG, HELD.

RECEIVED
JAN 03 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
DEC 23 2002
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE 1-3-03

WV. NO. 2003061031

Form CP-23