

1 060081

7-16

185 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,384.0000

C NE, SEC. 22, T 21 S, R 34 W/E

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Lang Well # 4

Operator: Petroleum Production Management, Inc.
Name:
Address: 209 E. William, Suite 200
Wichita, KS 67202

County Finney 89.53

Well Total Depth 2755 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 9:30 a.m. Day: 16 Month: 7 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-276-3286

were: 4 1/2" at 2755' w/325 sx cement, PBSD 2019', Perfs at 2647-52'

1st plug set CIBP at 2019',

2nd plug pump 10 sx gel and 80 sx cement at 1150',

3rd plug circulate cement from 400' to surface.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45 p.m. Day: 16 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2019' with 100' of fill,

2nd plug pumped 10 sx gel and 80 sx cement at 1150',

3rd plug circulated cement from 400' to surface.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 1200' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if ~~XXXXXX~~ observe this plugging.)

DATE 8-8-91

Signed [Signature] (TECHNICIAN)

DIV. NO. 32606