

6-13 15.055.10147.0001

To: 1 051317
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- Docket #E-9245

SE SE SE, SEC. 22, T 21 S, R 34 ~~WXX~~

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Lockman Well # 1

Operator: Petroleum Production Management, Inc.
Name & Address: 209 E. William, Suite 200
Wichita, KS 67202

County Finney 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service, Inc. License Number 6907

Address P.O. Box 458, Ness City, KS 67560

Company to plug at: Hour: 9 a.m. Day: 13 Month: 6 Year: 19 90

Plugging proposal received from Steve Park

(company name) Petroleum Production Management, Inc. (phone) 316-265-4651

were: 5 1/2" at 4650', 2 7/8" at 4240', PBTD 4155' No perfs open
1st plug run 1" tubing down 8 5/8" X 5 1/2" annulus, tag cement, cement to surface,
2nd plug run 1" tubing down 2 7/8" to 1299', pump 50 sx cement, pull tubing,
3rd plug run 1" tubing down 2 7/8" to 1190' and pump 35 sx cement, circulate to surface.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 13 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug ran 1" tubing down 8 5/8" X 5 1/2" annulus, tagged cement at 94', pulled tubing to 40' and cemented to surface,
2nd plug ran 1" tubing down 2 7/8" to 1299', pumped 50 sx cement, pulled 1" tubing, waited three hours and tagged cement at 1260',
3rd plug ran 1" tubing down 2 7/8" to 1190' and pumped 35 sx cement, circulated to surface.

Remarks: No casing recovery. Used Class H cement by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

STATE CORPORATION JUN 20 1990

DATE 7-2-90

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 28521

CONSERVATION DIVISION
Wichita, Kansas