

1 080494

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SW NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 4-2-56
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name R.C. Gates Well # 4 SWD
AKA Appl-Gate No. 7
County Stafford 136.01

Operator: Kaiser-Francis Oil Company
Name & Address P. O. Box 21468
Tulsa, OK 74121-1468

Well Total Depth 4185 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kaiser-Francis Oil Company License Number 6568
Address P. O. Box 21468, Tulsa, OK 74121-1468

Company to plug at: Hour: 10:00 am Day: 6 Month: March Year: 1986

Plugging proposal received from John Glenn
(company name) Kaiser-Francis (phone) 918-494-0000

were: 5 1/2" at 3857' PBTD 4185' Open Hole from 3857-4185' Perfs at 400' - 600 sx
1st plug RIH with tubing to 3040' and circulate cement to surface
2nd plug connect to SP/Casing annulus and take injection rate - if rate est., cement annulus.

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 12:45 pm Day: 6 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1/2 bbl down backside and pressured up to 250# Held.
2nd plug spotted 50 sx cement through tubing at 3081', pulled tubing to 2100' and spotted 50 sx cement, pulled tubing to 1500' and circulated cement to surface with 80 sx cement.
Pulled tubing all the way out and put swedge on 5 1/2". Pumped 65 sx cement and shut in at 200#.

Remarks: No Recovery. Used 60/40 Pozmix 6% gel by BJ-Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986
INV. NO. 13026
3-6

STATE CORPORATION COMMISSION Signed J. R. Me...
(TECHNICIAN)

MAR 20 1986
CONSERVATION DIVISION
Wichita, Kansas