

To: 1 120605
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-9 15.185.01757.0001 4 SP
API NUMBER 15- Drilled 7/50

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum, Inc.
Name &
Address 301 N. Main, Suite 900
Wichita, KS 67202

NW SW NW, SEC. 28, T 21 S, R 13 WXE
3630 feet from S section line
4950 feet from E section line

Lease Name Hufford "A" Well # 2
County Stafford 12/97

Well Total Depth 3753 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 173

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 9 Month: 8 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3753' w/100 sx cement, PBTB 3560', Perfs at 3387-3713' (7 sets)

1st plug sand back to 3330' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper plug
and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 9 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3340' and dumped 5 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-300 psi and shut in 200 psi. AUG 13 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2047' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
I did (XXXXXX) observe this plugging.

DATE 8-27-91
INV. NO. 32846

Signed *Richard Lacey*
(TECHNICIAN)