

15.145.00794.0000

1052265

TO: STATE CORPORATION COMMISSION

6-5

API NUMBER DRILLED 9-25-53  
NW SE NE, SEC. 34, T 21 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION

3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

1990  
990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PHINNEY RECEIVED WELL # 82

TECHNICIAN'S PLUGGING REPORT

COUNTY PAWNEE KANSAS CORP COMM 125.75

OPERATOR LICENSE # 5086

WELL TOTAL DEPTH 1999 JUN -9 @ 12:15 3869 FEET

OPERATOR: PINTAIL PETROLEUM, LTD

PRODUCTION CSG: SIZE 5 1/2" FEET 3866'

NAME AND ADDRESS 225 N MARKET #300 WICHITA, KS 67202

SURFACE CASING: SIZE 8 5/8" FEET 1023'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS & W WELL SERVICE, INC LICENSE NUMBER 6901

ADDRESS P. O. BOX 231, CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 5 MONTH: JUNE YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) DS & W WELL SERVICE INC. (PHONE) 316-587-3361

WERE: OPEN HOLE 3866' TO 3869'. TWO SUBMERSIBLE PUMPS LEFT IN WELL TOP OF FISH 3750'.

SAND BOTTOM TO 3700' AND PLACE 5 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

SPOT PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 1000' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT.

2ND PLUG AT 500' WITH 40 SX OF CEMENT. 3RD PLUG AT 40' WITH 10 SX OF CEMENT.

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 5 MONTH: JUNE YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3700' AND PLACED 5 SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 1000' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT

2ND PLUG AT 500' WITH 40 SX OF CEMENT,

3RD PLUG AT 40' WITH 10 SX OF CEMENT

GOOD CIRCULATION THROUGH OUT THE PLUG JOB.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 2000' OF 5 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey  
(TECHNICIAN) FORM CP-2/3

INVOICED  
DATE JUN 10 1998  
INV. NO. 50742  
6-5