

15.145.00784.0000 297 R

1120243

MAD 2 R 1000  
API NUMBER 15- Drill Completion Date 11/27/52

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SW, SEC. 34, T 21 S, R 16 W&E  
2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7230

Lease Name Dipman Well # 1

Operator: Hilliker Production  
Name & Address: 3315 16th Street  
Great Bend, KS 67530

County Pawnee 125.35

Well Total Depth 3857 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 900

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 28 Month: 3 Year: 19 89

Plugging proposal received from Joe Foelgner

(company name) Hilliker Production (phone) 316-793-7519

were: 5 1/2" at 3854' Open hole

RECEIVED  
STATE CORPORATION COMMISSION  
APR 4 1989

1st plug sand back to 3800' and dump 5 sx cement on top sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 28 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3800' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2437' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Duane Rankin  
(TECHNICIAN)

STW

DATE 4-19-89

INV. NO. 24336